



Maricopa County

Office of Procurement Services – Article 5
320 W. Lincoln Street
Phoenix, Arizona 85003

ADDENDUM NO. 3
TO MC85 at 83rd Ave and Center Turn Lane Exp 95th to 75th Ave
ADVANTAGE DOCUMENT ID# 180098-DBB
PROJECT OWNERS PROJECT/CONTRACT # TT0345

Addendum Date: August 8, 2018

County Project Owner: Maricopa County, Department of Transportation

MC85 at 83rd Ave and Center Turn Lane Exp 95th to 75th Ave, 180098-DBB is herein modified. The provisions of said documents applicable to these modifications remain unchanged unless specifically indicated otherwise.

This Addendum No. 3 forms a part of the solicitation/contract documents and modifies the clauses/provisions as follows:

1. **Solicitation** is changed to the following:

Replace the Special Provisions provided in the Solicitation with the attached updated TT0345 and TT0553 Special Provisions. A summary of the changes is:

- A. **105.6 COOPERATION WITH UTILITIES, Salt River Project (Irrigation)**, replace the seventh paragraph with the following: "Starting at MC 85 station 1237+37 and continuing west of 91st Avenue and north south along 91st Avenue, SRPI relocations cannot proceed until the USA Fee Land/Easement land exchange is completed. These areas are noted on the attached SRPI plan sheets labeled as Phase 1B. This will affect the construction schedule of the project improvements that need to be constructed over and adjacent to the existing SRPI pipelines to be relocated and removed. The roadway improvements throughout these areas of the project shall not begin without the approval of the Engineer. Expected completion of the USA Fee land exchange is December 31, 2018. For all irrigation relocation west of station 1237+37 additive alternate bid items have been added to the bid schedule as follows: 18" RGRCP, Class V (Additive Alternative Bid Item); 24" RGRCP, Class V (Additive Alternative Bid Item); 30" RGRCP, Class V (Additive Alternative Bid Item); 36" RGRCP, Class V (Additive Alternative Bid Item); 42" RGRCP, Class V (Additive Alternative Bid Item); 48" RGRCP, Class V (Additive Alternative Bid Item); SRPI Irrigation Manhole (Additive Alternative Bid Item); Headwall, Per

SRP Details, 1-24" Pipe (Additive Alternative Bid Item); Headwall, Per SRP Details, 1-36" Pipe (Additive Alternative Bid Item); Headwall, Per SRP Details, 1-42" Pipe (Additive Alternative Bid Item); Trash Rack, Per SRP Details (Additive Alternative Bid Item). No additional measurement or payment shall be made for construction delays or remobilization expenses incurred by the contractor to construct any of the improvements shown on the project plans or SRPI relocation design plans within this area of the project. Updated plans for Phase 1B are currently not available for distribution. Additional work at 79th Avenue is required but not currently shown in the plans provided with the bid package. Construction of these items will be handled as additional quantities under existing bid items."

- B. **205.2 Unsuitable Material, add the following:** "Existing asphalt pavement that needs to be removed within the roadway excavation areas shall be considered unsuitable material."
- C. **301.7 - Delete and replace the first paragraph with the following:** "No separate measurement will be made for stripping, scarifying, grading, excavating, hauling, filling, compacting, disposing of excess or unsuitable materials or pavement removal that is occurring in locations requiring subgrade preparation for new construction. The measurement and cost being included in item 205.01150 "ROADWAY EXCAVATION"."
- D. **301.7 - Delete and replace the last sentence of the third paragraph with the following:** "The measurement and cost being included in item 205.01150 "ROADWAY EXCAVATION."
- E. **309.5 - Delete and replace the last sentence with the following:** "The measurement and cost being included in item 205.01150 "ROADWAY EXCAVATION."

2. **Attachment A-1 Bid Schedule is replaced as follows:**

Replace attachment A-1 Bid Schedule with the attached revised schedule.

Changes include the following:

The quantity of bid Item 205.01150 Roadway Excavation is revised to 76,564 CY

Added Bid Items:

523.16124 "HEADWALL, PER SRP DETAILS, 1-24" PIPE" - 2 EACH

523.16125 "HEADWALL, PER SRP DETAILS, 1-24" PIPE (ADDITIVE ALTERNATIVE BID ITEM)" - 3 EACH

523.16136 "HEADWALL, PER SRP DETAILS, 1-36" PIPE (ADDITIVE ALTERNATIVE BID ITEM)" - 1 EACH

523.16142 "HEADWALL, PER SRP DETAILS, 1-42" PIPE (ADDITIVE ALTERNATIVE BID ITEM)" - 1 EACH

523.40124 "TRASH RACK, PER SRP DETAILS" - 2 EACH

523.40125 "TRASH RACK, PER SRP DETAILS (ADDITIVE ALTERNATIVE BID ITEM)" - 1 EACH

ALL OTHER PROVISIONS SHALL REMAIN IN FULL FORCE AND EFFECT.

Project Owner Approval:

By: BEN MARKERT

Signature: Ben Markert

Title: PROJECT MANAGER

Date: 8-8-2018

Included with your offer, your firm/company is required to acknowledge this addendum, and every addendum, relating to this solicitation by completing the following information:

Addendum No. 3 Acknowledgement:

Firm Name

Signature

Title

Signatory Printed Name

Date